HHS0009854 / 20-122-RSC Addendum 2 Questions

Question #	Question	Answer
1	Detail 1/D1 calls to nest the new deck over the existing deck. However, it also call out to paint the underside of the new deck. Please confirm if the entire underside of the existing deck is to be repainted as well.	Contractor is to paint underside of any new deck material installed. Existing deck materials is not to be repainted.
2	Please confirm if base bid is to include new deck over existing deck only at abandoned penetrations as shown in the drawings per detail 2/D1.	Replace decking at abandoned roof penetrations and at the cantilevered roof edge condition.
3	Per Detail 3/D2 please confirm if all cantilevered roof edge conditions are to get the metal deck entirely replaced.	Replace all decking at the cantilevered roof edge condition.
4	Please advise If it's acceptable to place the dumpster parallel to the roof line outside the fence area. If not, please specify approved location.	It is acceptable to place the dumpster parallel to the roof line in the location shown. However, the contractor will be required to put up temporary fencing around the dumpster in accordance with Uniform General Conditions/Supplementary General Conditions section 7.7.1.
5	3/D3 shows a steel angle to be removed below the roof blocking , what size replacement should be assumed?	No replacement of steel angle, attach new wood blocking to the decking.
6	Please confirm that unit cost will be used to determine added cost unforeseen issues such as decking within roofing that requires replacement.	Any roof deck replacement other than repairing abandoned roof penetrations and the cantilevered roof edge conditions are not to be included in the base bid proposal amount. The unit price provided will be used for any other roof deck replacement that is deemed necessary.
7	What testing if any will testing agency perform?	Owner reserves the right to engage a quality control testing agency to provide testing services for construction materials and methods as the owner deems necessary.